

1 060905

15.145.00975.0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-N/A
NE NE NE, SEC. 34, T 21 S, R 16 W/S
4645 feet from S section line
165 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4519

Lease Name Robert Bell Well # 1 SWD

Operator: Chevron U.S.A., Inc.
Name & Address P.O. Box 12116
Oklahoma City, OK 73157

County Pawnee 148.98

Well Total Depth 4584 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 980

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembrée Well Service License Number 6907

Address 302 E. Sycamore, Box 458, Ness City, KS 67560

Company to plug at: Hour: 2:30 p.m. Day: 24 Month: 11 Year: 1986

Plugging proposal received from Dink Clutts

(company name) Chevron (phone) 405-949-7000

were: 7" at 3975', 5 1/2" at 4012' PBD 4584' Open hole 3975' to 4584'

1st plug pump 8 sx hulls and 100 sx cement through tubing at 4001',

2nd plug tag cement with tubing at 2811', pump 8 sx hulls and 80 sx cement down 5 1/2".

Plugging Proposal Received by Paul Lüthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 4:30 p.m. Day: 24 Month: 11 Year: 1986

ACTUAL PLUGGING REPORT 1st plug pumped 8 sx hulls and 100 sx cement through tubing at 4001',

No one saw this plug.

2nd plug tagged cement with tubing at 2811', pumped 8 sx hulls and 80 sx cement down 5 1/2" -

got good returns out 10 3/4". Pressured up on 7" at 200 lbs. for 20 minutes.

Paul Luthi and J.H. Metz saw all the top plugging.

Remarks: Used Econolite cement w/2% cc by Halliburton on top plug. NOV. 26 1986
(If additional description is necessary, use BACK of this form.)

INVOICED (with check) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 12-3-86

INV. NO. 15449
11-24