

1 120956

15.145.00798.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 10/2/53

8-15

NE NE NW, SEC. 34, T. 7, R. 21 S, R. 16

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Weiman Well # 3

Operator: Pintail Petroleum, Ltd.

County Pawnee

Name & Address 225 N. Market, Ste. 300

Well Total Depth 3866 125.65 ft

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 980

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2 p.m. Day: 15 Month: 8 Year: 19 94

Plugging proposal received from Kevin Strube

(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 3853', PBTD 3855', Perfs at 3853-54'

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 7 sx gel, 50 sx cement, 13 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 15 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3800' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 7 sx gel, 50 sx cement, 13 sx gel, 200 lbs. hulls and 100 sx cement.

Pumping pressure 0-800 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION RECEIVED
AUG 19 1994
CONSERVATION DIVISION
WICHITA, KANSAS

(and/or ~~XXXXXX~~) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

INVOICED
DATE 9-6-94
INV. NO. 41107