

1010147

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,149-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 6330

Operator: Carl Boxberger

Name & Address P. O. Box 474

Great Bend, KS 67530

SW SW SE , SEC. 34 , T 21 S, R 16 (W) X
N SE Corner of

330 feet from section line

W SE Corner of

2310 feet from section line

Lease Name Fleske Well # 1

County Pawnee

Well Total Depth 3938 127.99 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 991

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Boger Brothers License Number 9421

Address 102 North Walnut, Hoisington, KS 67544

Company to plug at: Hour: 2:00 am Day: 7 Month: August Year: 19 84

Plugging proposal received from Dale Smith

(company name) Boger Brothers (phone) 316-984-4469

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3870' with 40 sx cement

2nd plug at 1025' with 50 sx cement

3rd plug at 500' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement. Plug water well with 15 sx cement

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 am Day: 7 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 3870' with 40 sx cement, 2nd plug at 1025' with 50
sx cement, 3rd plug at 500' with 50 sx cement, 4th & 5th plugs - solid bridge- hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement. Plugged water well with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form)

(If did not) observe this plugging.

INVOICED

DATE 8-17-84

INV. NO. 3184

P-7

SEP 11 1984

Signed Ken Beakus (TECHNICIAN) SA