

To: **1 120953**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-11

API NUMBER 15-4/3/53 15.145.00796.0000  
NE NW NW, SEC. 34, T. 7 S, R. 16 W  
4950 feet from S section 11  
4290 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086  
Operator: Pintail Petroleum, Ltd.  
Name: 225 N. Market, Ste. 300  
Address: Wichita, KS 67202

Lease Name Weiman Well # 1  
County Pawnee 128.83  
Well Total Depth 3964 ft  
Conductor Pipe: Size 12½ feet 1000  
Surface Casing: Size 8 5/8 feet 1012

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D.S.&W. Well Servicing, Inc. License Number 6901

Address 403 W. Ft. St., Claflin, KS

Company to plug at: Hour: 11 a.m. Day: 11 Month: 8 Year: 19 94

Plugging proposal received from Kevin Strube

(company name) D.S.&W. Well Servicing, Inc. (phone) 316-587-3361

Perfs: 5½" at 3844', Perfs at 3843-45', PBTD 3849'

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1030',

3rd plug pump 40 sx cement at 450',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30 p.m. Day: 11 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5½" casing back to 3790' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped through 5½" casing with 50 sx cement at 1064',

3rd plug with 40 sx cement at 460',

4th plug with 20 sx cement at 50-0'.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1994

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2003' of 5½" casing  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Please observe this plugging.

DATE 9-6-94

INV. NO. 41108

Signed Dean Rankin  
(TECHNICIAN)