

1 120955

8-15

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-21,122-0000

SW NE NW, SEC. 34, T 21 S, R 16  
4290 feet from S section 11  
3630 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License # 5086

Lease Name Wieman Well # 5

Operator: Pintail Petroleum, Ltd.

County Pawnee

Name: 225 N. Market, Ste. 300  
Address: Wichita, KS 67202

Well Total Depth 3905 126,91

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 989

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12:40 p.m. Day: 15 Month: 8 Year: 19 94

Plugging proposal received from Kevin Strube

(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 3903' w/125 sx cement, PBSD 3851', Perfs at 3847-50'

1st plug sand 5 1/2" casing back to 3795' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 7 sx gel, 50 sx cement, 13 sx gel,

100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 2 p.m. Day: 15 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3795' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 7 sx gel, 50 sx cement, 13 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-700 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing  
(if additional description is necessary, use BACK of this report.)

RECEIVED STATE CORPORATION COMMISSION  
AUG 19 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED

DATE 9-6-94  
INV. NO. 41106

Signed Duane Rankin (TECHNICIAN)