

15.145.00786.0001

SWD # C, 11-782

1 030598

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- dry before 1965 R

NW, SEC. 34, T 21 S, R 16 W/6  
2970 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7230  
Operator: Hillikey Production Co.  
Name &  
Address 5207 Teelston  
Great Bend KS. 67530

Lease Name Fairbanks Well # 2 SWD  
County Pawnee 134.45  
Well Total Depth 4137 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 7/8 feet 950

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hillikey Production Co. License Number 7230

Address 5207 Teelston Great Bend KS. 67530

Company to plug at: Hour: 9:00 AM Day: 26 Month: 11 Year: 19 85

Plugging proposal received from Joe Folkner

(company name) Hillikey Production Co. (phone) 793-2788

were: 5 1/2" @ 3865' w/ 150SX - 4 1/2" liner 3853-3910' TOP of cement on 5 1/2" @ 2815  
open hole completion from 3910-4137' Taking pocket - TOP of Fish WA  
1st plug @ 2800' w/ 50SX cement + 2SX Flow seal w/ last 15SX mixed w/ balls -  
(holes may be in pipe from 1600'-2200')  
2nd Circ hole w/ mud and spot 25SX @ 975' 3rd plug - 300' w/ 20SX -

4 1/2" 0-40 w/ 10SX Plugging Proposal Received by Don Ubel - SA  
6 1/4 pump 150SX down annulus. (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00 PM Day: 30 Month: 11 Year: 19 85

ACTUAL PLUGGING REPORT Ron taking to 2834' and pump 75SX + 1 ball

(TOP of cement inside casing was 2343' top)

2nd plug - mud to 975' + spot 25 SX cement - (lost to formation -)

3rd Set old packer @ 900' + Spot cement on packer w/ 50SX - TOP of cement @ 430'

4th Spot cement @ 300' w/ 50SX circulated to 0' -

Cement not pump down annulus - tested w/ 500 # - would not take fluid.

Remarks: \_\_\_\_\_  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DEC 11 1985

RECEIVED  
STATE CORPORATION COMMISSION  
Signed Stoughlum -  
(TECHNICIAN)

DATE \_\_\_\_\_

DEC 5 1985

INV. NO. 11432

11-30 JAN 15 1986 CONSERVATION DIVISION  
Wichita, KS