

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-19276-00-02
Spot: NWNWSW Sec/Twnshp/Rge: 23-11S-15W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DREHER Well #: 2
County: RUSSELL Total Vertical Depth: 600 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	600		75 sx
SURF	8.625	195		150 sx

Well Type: SWD UIC Docket No: D21072.0 Date/Time to Plug: 08/21/2017 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/10 sx hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/21/2017 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 525' and pumped 60 sx cement. Circulated good cement to pit. POOH. Filled casing with 15 sx cement. Hooked to casing and pumped 5 sx cement at 450 psi. Shut in pressure 400 psi. Braden head was dug out and found to be full of cement.
08/22/2017 - Cement to surface. Cut casing off 3' below surface. Filled pit and cellar. Well site leveled off.

GPS: 39.08104 -098.96214

Done

Remarks: QUALITY WELL SERVICE TICKET # 6130 21ST CENTURY FEE FUND PROJECT CONTROL # 20170021-001

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

KCC WICHITA

SEP 12 2017

SEP 28 2017

Form CP-2/3

RECEIVED