

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-21128-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 6-13S-13W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HOLLAND Well #: 1  
County: RUSSELL Total Vertical Depth: 3169 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 266 N MAIN ST, STE 220  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3169		200 sx
SURF	8.625	247		165 sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2017 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: KANSAS CORPORATION COMMIS Phone: (620) 727-3409

Proposed Plugging Method: Ordered 1350 sx 60/40 pozmix 4% gel cement, 1500 # hulls and 300 # Calcium Chloride (C.C.)

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/29/2017 10:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

08/28/2017

Perfs:

08/22/2017 - Rigged up. Ran sand line bar in and stopped at 280'.  
08/23/2017 - Ran tubing with notch collar in and worked down to 1025'. Lost fluid all day. District supervisor and E.C.R.S. were notified that well blew out at 1800 hour.  
08/24/2017 - Checked on well. Well was dead and tubing was hung in the hole. Pumped 75 sx cement followed by 225 sx cement w/200 # hulls. Well went on vacuum and started to blow. Shut in and WOC. Opened valve and pumped 200 sx cement w/200 # hulls. Displaced tubing and shut in.  
08/25/2017 - Tubing had a slight blow. Pumped 200 sx cement w/250 # hulls. Displaced tubing and shot off at 356'. Pumped 100 sx cement and well went on vacuum. POOH. Hooked to casing and pumped 200 sx cement w/250 # hulls. Shut in.  
08/28/2017 - Pumped 150 sx cement w/3% c.c. and 250 # hulls. WOC. Pumped 125 sx cement w/3% c.c. w/250 # hulls. Braden head started to circulate. Pumped 30 sx cement and had good cement circulation. Closed braden head and pressured casing to 1000 psi. Shut in.  
08/29/2017 - Cut off casing. Cement was down 3' in casing and 5' on backside. Topped off w/10 sx cement. Closed pit and cellar. Restored the site.

GPS: 38.9844 -098.80680

Remarks: QUALITY WELL SERVICE TICKET # 6131 21ST CENTURY FEE FUND PROJECT CONTROL # 20170021-002

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

OCT 17 2017

RECEIVED

SEP 29 2017