

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21187-00-00
Spot: S2N2SE Sec/Twnshp/Rge: 6-13S-13W
1541 feet from S Section Line, 1186 feet from E Section Line
Lease Name: HOLLAND Well #: 2
County: RUSSELL Total Vertical Depth: 3313 feet

Operator License No.: 101

String Size Depth (ft) Pulled (ft) Comments

Op Name: KCC FEE FUND PLUG

PROD 4.5 3313 200 sx

Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

SURF 8.625 264 175 sx

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/30/2017 10:30 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: KANSAS CORPORATION COMMIS

Phone: (620) 727-3409

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement, 500 # hulls and 300 # calcium chloride (c.c.)

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/31/2017 5:30 PM

KCC Agent: RAY DINKEL

08/30/2017

Actual Plugging Report:

Perfs:

08/30/2017 - Ran rod line bar and tagged at 2931'. Cut tubing head off and found 2 7/8" tubing in bad condition. Pumped 40 sx cement and displaced 7 1/4 bbls with a little pressure. Ran in with tubing gun and had trouble getting down tubing. Perforated at 700', 350' and 200'. Hooked to casing and pumped 150 sx cement. Well was on slight vacuum.
08/31/2017 - Pumped 75 sx cement w/3% c.c. w/150 # hulls. Pressured slowly to 1000 psi. Shut in pressure 800 psi. Hooked to braden head and pumped 30 sx cement at 300 psi. Shut in. Cut off head. Closed cellar and pit. Restored the location.

GPS: 38.94792 -098.80273

Remarks: QUALITY WELL SERVICE TICKET # 6132 21ST CENTURY FEE FUND PROJECT CONTROL # 20170021-003

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

OCT 17 2017

RECEIVED

SEP 29 2017