

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- -

NW, SEC. 16, T21 S, R 7 W/E

1650 FEET FROM N/S SECTION LINE

1650 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6050

LEASE NAME Stange WELL # 4-H

OPERATOR: K&K Oil Co. (Kelso Casing Pulling)  
NAME & ADDRESS Box 347  
Chase, Kansas 67524

COUNTY Rice

WELL TOTAL DEPTH 3387 <sup>\$110.08</sup> FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET \_\_\_\_\_

SURFACE CASING: SIZE 8 5/8 FEET 108

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NUMBER 6050

ADDRESS Box 347, Chase, Kansas 67524

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 15 MONTH: July YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Mike Kelso

(COMPANY NAME) Kelso Casing Pulling (PHONE) 316 938 2457

WERE: Fill hole with sand to 3100' and cement with 5 sacks  
Cement. Squeeze hole with 5 sacks hulls, 20 sacks gel-mud,  
and 100 sacks 50/50 Permox w/4% gel. Pump into 8 5/8" surface  
Casing.

PLUGGING PROPOSAL RECEIVED BY [Signature]  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 15 MONTH: July YEAR: 1983

ACTUAL PLUGGING REPORT \_\_\_\_\_

Same as above

REMARKS: 2818.79' of 5 1/2" casing recovered  
Allied Cementing Co, Inc. 26249

RECEIVED  
STATE CORPORATION COMMISSION

JUL 19 1983

CONSERVATION DIVISION  
Wichita, Kansas

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

SIGNED [Signature]  
(TECHNICIAN)

INVOICED  
DATE 7-25-83  
INV. NO. 4942-W