

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name F. G. Holl

Complete Address: 6427 E. Kellogg, Wichita, Kansas

Lease Name Snider Well No. # 1

Location App. E/2 SE NW Sec. 3 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3439'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: 1809 Lakin, Great Bend, Kansas License No. 462

Operation Completed: Hour 11:30AM Day 29th Month April Year 1963

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cemented with 200 sacks. 3439' of 4 1/2"
long string, cemented with 50 sacks. Plugged back to 3160'. Perferated
from 3110' to 14'. Sanded to 3100', cemented with 3 sacks. Plug was
set at 225', 10' rock bridge, cemented with 3 sacks and let set over
night, bailed hole down next morning, and finished cementing with 17
sacks on plug. Filled hole with mud to 40', 10' rock bridge, cemented
with 10 sacks to base cellar.

2000' Of 4 1/2" long string recovered from hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elwing
Well Plugging Supervisor

DATE 5/1/63

INV. NO. 6988-W