

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

OR  
FORMATION PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Blitting Building  
Wichita, Kansas

Strike out upper line  
when reporting plug-  
ging off formations.

Rice County. Sec. 5 Twp. 21 Rge. 7 (E) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NE NE NE  
Lease Owner Petroleum, Inc.  
Lease Name Willhaus Well No. 1  
Office Address 100 Derby Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 7, 1950  
Application for plugging filed December 7, 1950  
Application for plugging approved December 7, 1950  
Plugging commenced December 7, 1950  
Plugging completed December 7, 1950  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3373' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 227'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Wooden plug set at 227'. Cemented and displaced through drill pipe 15 sax. Filled hole with heavy mud to 30'. Placed wooden plug at 30'. Filled to surface with cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1950  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum, Inc.  
Address 100 Derby Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Eric H. Jager (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager  
100 Derby Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of December, 1950

Charlotta Skidman  
Notary Public.

My commission expires October 13, 1954

PLUGGING  
FILE SEC 5 T 21 R 7 W  
BOOK PAGE 47 LINE 32

WILLHAUS WELL #1

|                |             |                          |   |
|----------------|-------------|--------------------------|---|
| Casing Record: | COMPANY:    | Petroleum, Inc.          | Description:                                |
| 8-5/8" - 127'  | CONTRACTOR: | Aylward Drilling Company | NE NE NE Sec. 5-21-7<br>Rice County, Kansas |
|                | COMMENCED:  | Nov. 23, 1950            | Elevation:                                  |
|                | COMPLETED:  | Dec. 7, 1950             | Potential: D. & A.                          |

| <u>Formation</u>  | <u>From</u> | <u>To</u> | <u>Remarks</u>                  |
|-------------------|-------------|-----------|---------------------------------|
| Surface           | 0           | 20        |                                 |
| Sand              | 20          | 80        |                                 |
| Red Bed and Shale | 80          | 127       | Set 8-5/8" surface pipe at 127' |
| Shale and shells  | 127         | 650       | and cemented with 100 max.      |
| Salt and shale    | 650         | 965       |                                 |
| Shale and lime    | 965         | 1320      |                                 |
| Sandy lime        | 1320        | 1345      |                                 |
| Lime and shale    | 1345        | 2285      |                                 |
| Shale and shells  | 2285        | 2410      |                                 |
| Lime sandy        | 2410        | 2440      |                                 |
| Lime              | 2440        | 3150      |                                 |
| Lime and shale    | 3150        | 3190      |                                 |
| Lime              | 3190        | 3230      |                                 |
| Lime broken       | 3230        | 3280      |                                 |
| Lime              | 3280        | 3353      |                                 |
| Chert & Lime      | 3353        | 3364      |                                 |
| Lime              | 3364        | 3373      |                                 |
|                   |             | 3373'     | T.D.                            |

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1950  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

*Al Skalsky*  
Al Skalsky

Subscribed and sworn to before me this 11th day of December, 1950.

*Harold Casper*  
Notary Public

My commission expires  
July 16, 1952.

PLUGGING  
NE NE NE SEC 5-21-7  
RICE COUNTY, KANSAS  
DATE 47 1950