

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rice County. Sec. 5 Twp. 21 Rge. (E) 7 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SWc SW NE $\frac{1}{4}$

Lease Owner Lauck & Moncrief and Wolf Creek Oil Co.

Lease Name Willhaus Well No. 2

Office Address 520 Fourth National Bank Bldg. Wichita, Kans.

Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date, well completed Aug. 22 193 9

Application for plugging filed Aug. 22 193 9

Application for plugging approved Aug. 22 193 9

Plugging Commenced Aug. 22 193 9

Plugging Completed Sept. 1 193 9

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well Durkee

Producing formation NONE Depth to top Bottom Total Depth of Well 3362 Feet.

Show depth and thickness of all water, oil and gas formations.



OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Conglomerate	no	3325	3353	10"	96'	none
				7"	3325	1336

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

cement 3362 - 3310  
heavy mud 3310 - 100'  
cement 100 84'  
mud 84 10' below cellar  
cement to base of cellar



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lauck & Moncrief  
Address 520 Fourth National Bank Bldg. Wichita, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
E. C. Moncrief (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. C. Moncrief

Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of September 19 39

My commission expires Sept. 14, 1939

Notary Public

LAUCK & MONCRIEF and WOLF CREEK OIL COMPANY

No. 2 Willhaud

Sec. 5-21-7W

SWc NE

Commenced Aug. 2, 1939

Completed Aug. 22, 1939

10" 96' cemented with 60 sacks  
7" 3325 cemented with 50 sacks

surface	15
sand	35
sand & clay	70
red rock	180
shale & shells	435
shale & red rock	460
shale & shells	715
shale & salt	963
shale & shells	1010
shale & lime	1200
broken lime	1280
lime & shale	1381
lime	1545
lime & shale	1735
shale & shells	1930
lime & shale	1950
shale & shells	2292
lime	2308
shale & shells	2405
lime	2510
broken lime	2585
lime	2725
broken lime	2740
shale & shells	2870
shale	2890
lime	3255
Lime & shale	3324 $\frac{1}{2}$
Conglomerate	3326
3326 - -	3327 SLM
Corrected to Derrick floor	
Top Conglomerate	3325
rotary T.D.	3326
Standardized	
Top cement	3308
bottom casing	3325
T. D.	3326
Conglomerate	3331
Rainbow	
Conglomerate	3335
Bariegated shale	3343 core
Conglomerate	3353
slight increase oil	
Chat white	3362 T.D.

D&amp;A

PLUGGING		
FILE	SEC-5-T-21-R-7W	
BOOK	PAGE 72	LINE 44

