


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

9

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 8 Twp. 20 Rge. 24 (W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Pickrell Drilling Company
Lease Name Betz "B" Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 21, 19 65
Application for plugging filed January 21, 19 65
Application for plugging approved January 21, 19 65
Plugging commenced January 21, 19 65
Plugging completed January 21, 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with
20 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebitts

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 4th National Bank Building, Wichita 2, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 65

Maxine Blackman
Maxine Blackman, Notary Public.

My commission expires June 21, 1966

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Building
Wichita, Kansas

Rotary Drilling Commenced 1--8-65
Rotary Drilling Completed 1-21-65

LOCATION: Betz "B" No. 1, C SE NW Section 8-20S-24W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (12 jts) 8 5/8" surface casing set at 250', cemented with 165 sacks cement. Circulated. Completed 3 P.M. January 8, 1965. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

30	Sandy Soil	<u>C. F. S.</u>
270	Shale & Shells	4270
1320	Shale, Shells & Sand	4280
1535	Shale & Shells	4350
1570	Anhydrite	4353
1705	Shale & Shells	4358
2210	Shale & Lime	4363
2875	Lime	4368
3750	Lime & Shale	4371
4280	Lime	4375
4450	Mississippi - RTD	4379

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1965

CONSERVATION DIVISION
Wichita, Kansas

Slope Tests

- 2500
- 3000
- 3500
- 4000

S. L. M.

- 3840
- 4165
- 4393

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 27th day of January, 1965, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

Maxine Blackman
Maxine Blackman, Notary Public

My commission expires: June 21, 1966