


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County. Sec. 8 Twp. 20 Rge. 24 (E) W (W)
Location as "NE/CNW&SW" or footage from lines C NE SW
Lease Owner Mack Oil Company
Lease Name Miller Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 3/25/66 19
Plugging completed 3/29/66 19
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 4405 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	274	none
				4 1/2	4391	511'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Raised mast, pulled rods, had trouble getting pump unseated.
~~STARTED~~ pulling tubing, sand hole to 4380' and set 4 sacks of cement.
Cleaned cellar, rigged up on 4 1/2 casing. Shot pipe at 609' and 512',
worked loose and pulled 17 joints of 4 1/2. Cut braden head off.
Tried to bail hole down, set rock bridge at 270' and set 2 sacks of
cement. Bailed hole down & dumped 23 sacks of cement. Mudded to 40'
set rock bridge and ran 10 sacks of cement to X base of cellar.

RECEIVED
12-20-66
DEC 20 1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 19 day of Oct, 1966

My commission expires Oct 22, 1970
Notary Public

MACK OIL COMPANY

15.135.19180.0000

Duncan, Oklahoma

DRILLERS WELL LOG

William Miller #1

C NE SW Sec. 8-20S-24W

Ness County, Kansas

Commenced R.D.: 5-31-64

Elevation: 2326 KB

Completed R.D.: 6-11-64

Initial Production: Oil

Total Depth: 4400'

Contractor: Mack Oil Company

STRATA	DEPTH
Shale	0 - 1045
Sand	1045 - 1300
Shale	1300 - 1325
Shale & Lime	1325 - 1923
Shale	1923 - 2211
Shale & Lime	2211 - 2450
Lime	2450 - 3074
Shale & Lime	3074 - 3235
Lime	3235 - 3493
Shale & Lime	3493 - 3698
Lime	3698 - 3728
Shale & Lime	3728 - 3821
Lime	3821 - 4405

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1966

CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Robert L. Harris

Signed and sworn to in my presence this 23rd day of June, 1964, by Robert L. Harris, representative of Mack Oil Company.

Henry Alder

Notary Public

Commission expires: July 24 1967