

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-35-21,885-0000

LEASE NAME Miller

WELL NUMBER 1

SPOT LOCATION NE NE SW

SEC. 8 TWP. 20 RGE. 24 (X) or (W)

COUNTY Ness

Date Well Completed 10-10-1980

Plugging Commenced 11-24-1988

Plugging Completed 11-30-1988

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Reach Oil Corp.

ADDRESS 229 E. William, Suite 500, Wichita, Ks. 67202

PHONE # (316) 262-1515 OPERATORS LICENSE NO. 8572

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation MISS Depth to top 4360 bottom 4386 T.D. 4442

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	243'	0'
Production				4 1/2"	4442'	2100'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Squeeze perforations w/ 50 Sks. cement, pressured to 700 lbs. - Pump 50 sks. cement 1400' to 1200', mud 1200' to 780', Pump 80 sks. cement 780' to 400', mud to 280', Pump 40 sks. cement 280' to top. Put bridge & 10 sks. cement 40' to 3' Cut off 8 5/8", 3' Below ground level & cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6437

Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves ~~operator~~ or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 2nd day of Dec., 1988

Sondra L. Eves
Notary Public

My Commission expires: 12-6-88

