

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-21,687.0000

LEASE NAME Betz #2

WELL NUMBER _____

SPOT LOCATION C SW NE

SEC. 6 TWP. 20S RGE. 24W (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 5-16-86

Plugging Completed 5-21-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market Suite 1110, Wichita, Kansas 67202

PHONE # (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4416'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	605'	none
				4-1/2"	4405'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4350' and 4 sacks cement. Shot pipe @2814', 2421', 2000', 1731', 1509', 1258', 1005', 940', 812', no pipe recovery. Pumped 300 sacks 60/40 Pos. 6% gel down 4-1/2" casing. Tied onto anulus, PSI to 500# standing, pumped 100 more sacks 60/40 pos, 6% gel down 4-1/2" casing. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 5050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 86

My Commission expires: _____



Irene Hoover
Notary Public

STATE CORPORATION COMMISSION
MAY 29 1986
CONSERVATION DIVISION
Wichita, Kansas

15.135.21687.0000

STATE COURT WICHITA, KANSAS

APR - 7 1986

CONSERVATION DIVISION
Wichita, Kansas**GREAT GUNS***R. A. Guard Log*

FILE NO.	COMPANY VINCENT OIL CORPORATION			
<i>MARKED</i>	WELL BETZ #2			
	FIELD			
	COUNTY NESS STATE KANSAS			
LOCATION: C-SW-NE			OTHER SERVICES	
SEC 6 TWP 20S RGE 24W				
Permanent Datum GROUND LEVEL Elev. 2399			Elevations: KB 2344	
Log Measured from KELLY BUSHING 5 Ft. Above Permanent Datum			DF	
Drilling Measured from KELLY BUSHING			GL 2339	
Date 9/19/79	GAMMA RAY	NEUTRON	GEARD	CALIPER
Run No.	ONE	ONE	ONE	ONE
Depth-Driller	4413	4413	4413	4413
Depth-Logger	4416	4416	4416	4416
Bottom Logged Interval	4407	4415	4411	4404
Top Logged Interval	00	00	3600	3600
Casing - Driller	85/8 @ 605	@	@	@
Casing-Logger	85/8 605			
Rm Size	7 7/8			
Type Fluid in Hole	DRISPAC DRLG MUD			
Density and Viscosity	9.9 41			
pH and Fluid Loss	10 15 cc	cc	cc	cc
Source of Sample	FLOW LINE			
Rm @ Meas. Temp.	.55 @ 75 °F	@ °F	@ °F	@ °F
Rmf @ Meas. Temp.	.4 @ 75 °F	@ °F	@ °F	@ °F
Rmc @ Meas. Temp.	.8 @ 75 °F	@ °F	@ °F	@ °F
Source of Rmf and Rmc	CHARTS			
Rm @ BHT	.36 @ 114 °F	@ °F	@ °F	@ °F
Time Since Circ.	2 HOURS			
Max. Rec. Temp. Deg. F	114 °F	°F	°F	°F
Equip. No. and Location	25 HAYS			
Recorded By	R. WOLF			
Witnessed By	MR. ROBY			

REMARKS