

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 36 Twp. 20S Rge. 26 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SW SE NW

Lease Owner Antares Oil Corp.
Lease Name McVickers Well No. 1


Office Address 1546 Cole Blvd - Suite 220, Golden, Colo.
Character of Well (Completed as Oil, Gas or Dry Hole) 80401

Dry Hole
Date Well completed 9-15 1980
Application for plugging filed 9-15 1980
Application for plugging approved 9-15 1980
Plugging commenced 9-15 1980
Plugging completed 9-15 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4460'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	302'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set,

- 920', plug, 70 sx cement
- 300', plug, 40 sx cement
- 40', plug, 10 sx cement
- 5 sx cement in rathole


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas - Suite 500, Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1980
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Kansas
Ernest Sifford (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas - Suite 500, Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 80.



Carolyn J. Tjaden
Carolyn J. Tjaden Notary Public.

My commission expires

OPERATOR: ANTARES OIL CORPORATION, 1546 Cole Blvd. - Suite 220, Golden, Colorado 80401
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name McVickers Well No. 1

Sec. 36 T. 20S R. 26W Spot C SW SE NW

County Ness State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 302' with 200 Sxs. 2% Gel
3% CC

Production: _____ @ _____ with _____ Sxs.

Type Well: D & A Total Depth 4460'

Drilling Commenced: 9-6-80 Drilling Completed 9-15-80

Formation	From	To	Tops
Cellar	0	7	
Sand	7	25	
Shale, Lime	25	302	
Shale	302	416	
Shale, Lime	416	3135	
Lime	3135	3413	
Shale, Lime	3413	3709	
Lime	3709	3933	
Shale, Lime	3933	4171	
Lime	4171	4460	

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1980
CONSERVATION DIVISION
Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log _____ Type and Depths Covered _____