


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit,
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 35 Twp. 20S Rge. (E) 26 (W)
Location as "NE/CNW'SW" or footage from lines C NE NE
Lease Owner O. A. Sutton
Lease Name Martha Well No. 1
Office Address 800 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 8 1975
Application for plugging filed July 8 1975
Application for plugging approved July 8 1975
Plugging commenced July 8 1975
Plugging completed July 8 1975
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4455 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	360'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 660' with 70 sacks. Plug at 300' with 20 sacks. Plug at 40' bridge and 10 sacks. Job complete at 7:15 a.m. 7-8-75.
Job by Howco.

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1975

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack G. Paulsen (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen
800 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of July, 1975.

My commission expires June 28, 1978.

Jean S. Taylor
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Martha #1
 C-NE-NE Sec 35-20S-26W
 Ness County Kansas

Commenced: 6-28-75

Completed: 7-8-75

OPERATOR: O. A. SUTTON

Depth		Formation	Remarks
From	to		
0	360	Clay-Blue Clay	Ran 9 jts of 28# 8 5/8" csg set @ 360' Cemented w/ 225 sks Common 2% Gel 3% CG PD @ 12:15 a.m. 6-29-75
360	480	Shale	
480	500	Sand	
500	615	Shale	
615	1073	Shale-Sand stks	
1073	1083	Blaine	
1083	1385	Sand	
1385	1649	Shale-Shells-Redbed	
1649	1975	Redbed-Anhy	
1975	2190	Shale-Shells	
2190	2435	Lime-Shale	
2435	2595	Shale-Lime	
2595	3638	Lime-Shale	
3638	4455	Lime	

4455 - TD

DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled C-NE-NE Sec 35-20S-26W, Ness County Kansas to the best of my knowledge and belief.

James S. Sutton II
 JAMES S. SUTTON II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 16th day of July 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I Have hereunto set my hand and official seal the day and year last above written.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.



RECEIVED
 STATE CORPORATION COMMISSION

JUL 21 1975

CONSERVATION DIVISION
 Wichita, Kansas