

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 35 Twp. 20S Rge. (E) 26 (W)

Location as "NE/CNW/SW" or footage from lines 150' SE of C SE NE

Lease Owner O. A. Sutton

Lease Name Martha Well No. 2

Office Address 800 Sutton Place, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 27 1975

Application for plugging filed August 27 1975

Application for plugging approved August 27 1975


Plugging commenced August 27 1975

Plugging completed August 27 1975

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4433 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	365'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug at 660' with 70 sacks; plug at 300' with 20 sacks; plug at 40' with solid bridge and 10 sacks. Job complete at 7:45 p.m. 8-27-75. Job by Halliburton.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 08 1975 9-8-75

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.


Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Elbie G. McNeil

(employee of owner) ~~xxx xxx xxx xxx xxx~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) \_\_\_\_\_

Elbie G. McNeil  
800 Sutton Place, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 28th day of June, 1978.

My commission expires June 28, 1978.

Jean S. Taylor

Notary Public.

GABBERT-JONES, INC  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Martha #2  
 150' SE of C-SE-NE Sec 35-20S-26W  
 Ness County Kansas

Commenced: 8-13-75

Completed: 8-27-75

OPERATOR: O. A. SUTTON

Depth		Formation	Remarks
From	To		
0	50	Top Soil-Clay	Ran 9 jts of used 28# 8 5/8" csg set @ 365' Cemented w/250 sks Common 2% Gel-3% CC PD @ 9:15 p.m. 8-13-75
50	128	Post Rock	
128	370	Shale	
370	1025	Shale-Redbed	
1025	1037	Blaine	
1037	1060	Shale-Redbed	
1060	1071	Blaine	
1071	1136	Shale	
1136	1665	Sand	
1665	1688	Anhy	
1688	2130	Shale	
2130	2560	Shale-Lime	
2560	4090	Lime-Shale	
4090	4433	Lime	DRY & ABANDONED

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 08 1975  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, James S. Sutton II, certify this is a correct copy of the Driller' Log for the well drilled 150' SE of C-SE-NE Sec 35-20S-26W, Ness County, Kansas to the best of my knowledge and belief.

*James S. Sutton II*  
 JAMES S. SUTTON II

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 5th day of September, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

