

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ness SEC. 25 TWP. 20S RGE. 21W E/W
Location as in quarters or footage from lines:

NE SW

Lease Owner Pickrell Drilling Company
Lease Name Wells D-E #2 Well No. _____
Office Address 205 Litwin Bldg. 110 N. Market Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 3-2-82
Plugging completed 3-9-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 4376'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	260'	none
				5-1/2"	4366'	496'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4332' and ran 6 sacks cement, picked up on pipe
and it parted, had to have starting nipple welded in, shot casing @3005', 2507',
2008', 1501', 951', 855' and 508'. Pulled a total of 16 joints of pipe. Plugged
well with 4 sacks hulls, 10 sacks gel, 70 sacks 50/50 pos, 4% gel, 3% cc., 1 sack hulls,
10 sacks gel, 8-5/8" plug, 70 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 82

My Commission expires:



Irene Hoover RECEIVED
Notary Public

APR - 5 1982

CONSERVATION DIVISION
Wichita Kansas

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
205 Litwin Building, 110 North Market
Wichita, Kansas 67202
LOCATION: #2 Wells 'D-E'
C NE SW, Sec. 25-20S-21W
Ness County, Kansas
CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

Rotary Drilling Commenced 4-21-66
Rotary Drilling Completed 4-28-66

RECEIVED
STATE CORPORATION COMMISSION

OCT - 1 1981

CASING RECORD: Surface csg, 8" at 260'. Production csg, 5 1/2"

CONSERVATION DIVISION
Wichita, Kansas

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Post Rock	100
Shale & Shells	261
Red Beds & Shale	750
Blain	768
Shale & Shells	2005
Shale & Lime	2345
Lime & Shale	2450
Lime	2665
Lime & Shale	2850
Shale & Lime	3280
Shale	3540
Shale & Lime	3700
Lime & Shale	3835
Lime	4100
Lime & Shale	4376

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By *C. W. Sebitts*
Attorney-in-Fact
C. W. Sebitts

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 29th day of September, 1981, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

Commission expires:

JANA LEA SCHNEWEIS
Notary Public
Sedgwick County, Kansas
December 9, 1982

Jana Lea Schneewis
Notary Public
Jana Lea Schneewis