

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

15.135.22215.0000

API NUMBER 15-135-22215-20

LEASE NAME Martin

WELL NUMBER #1

660 Ft. from N Section Line

1320 Ft. from E Section Line

SEC. 25 TWP. 20 RGE. 21 W or (W)

COUNTY Ness

Date Well Completed July 1982

Plugging Commenced 11-22-2000

Plugging Completed 11-22-2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Wilton Petroleum

ADDRESS 901 King Ave. Nyssa

PHONE(S) (316) 947-3250 OPERATORS LICENSE NO. 7775

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Oct, 1, 2000 (date)

by Mike Majer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? no

Producing Formation Mississippi Depth to Top 4390 Bottom 4400 T.D. 4425

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS 1 CASING RECORD 4 1/2 to 4425

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP at 3000ft w/ 2sks cement on top. Perf at 700 ft, mixed 125sks
cement & 1sk hulls. Pumped 25sks down annulus & pressured to 500PSI
Topped off w/ 3sks w/ 35sks
185sks 60/40 poe w/ 6% gel
Cement tickets enclosed

Name of Plugging Contractor Swift Services Inc License No. 32382

Address P.O. Box 466 - Ness City, Ks. 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: _____

STATE OF Kansas COUNTY OF Ness, ss. JAN 24 2001

TED J. Fuchs (Employee of Open Space Conservation Division)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed and
the same are true and correct, so help me God.

(Signature) Ted J. Fuchs

(Address) P.O. Box 466 Ness City, Ks.

SUBSCRIBED AND SWORN TO before me this 22 day of Jan, 2001

Ronald J. Stoecklein
Notary Public

My Commission Expires: 7-10-04

Notary Public
Ronald J. Stoecklein
NOTARY PUBLIC
State of Kansas
MY APPT. EXPIRES

OR
Form CP-1
Revised 05-82



CHARGE TO: Wilton Petroleum
 ADDRESS:
 CITY, STATE, ZIP CODE: Nyssa, Or.

TICKET No 3010

15-135-22215-0000

PAGE 1 OF 1

SERVICE LOCATION: 1. Nyssa City
 WELL/PROJECT NO.: #1-9 SWD LEASE: Martin COUNTY/PARISH: Nyssa STATE: Ks CITY: Nyssa City, Ks DATE: 11-22-2000 OWNER: Same
 2. TICKET TYPE: SERVICE SALES CONTRACTOR: none RIG NAME/NO.: SHIPPED VIA: DELIVERED TO: ORDER NO.:
 3. WELL TYPE: oil WELL CATEGORY: workover JOB PURPOSE: old well Plug to Abandon 2-wells WELL PERMIT NO.: WELL LOCATION:
 4. REFERRAL LOCATION: INVOICE INSTRUCTIONS:

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UM		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE	104	30	mi		2.50	75.00
576		1			Pump Service		1	ea		500.00	500.00
580		1			Addition of Hours	2 nd well	3	hrs		100.00	300.00
275		1			Cotton Seed Hulls		3	sk		15.00	45.00
328		1			60/40 Pozmix	62 gal	330	sk		5.65	1864.50
581		1			Service Charge Cement		350	sk		1.00	350.00
583		1			Drayage	Cement	449	lb	Ton miles	.75	336.75

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X
 DATE SIGNED: 11-22-2000 TIME SIGNED: 09:00
 A.M. P.M.

REMIT PAYMENT TO:

SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				3471.39
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX
ARE YOU SATISFIED WITH OUR SERVICE?	<input type="checkbox"/> YES	<input type="checkbox"/> NO		TOTAL
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: [Signature] APPROVAL:

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 11-22-2000 PAGE NO. 27

CUSTOMER Wilton Petroleum WELL NO. #14 LEASE Martin JOB TYPE Plug to Abandon TICKET NO. 3010

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T.	C.	TUBING	CASING	
								Called out
								On location / Martin
	09:00							Set CIBP & 2 sks cut at 30000
								Perf at 700 ft
	10:00							Pump injection rate 2 bbl at 100 PSI
	11:00							Mixed 125 sks cut & 1 sk Hull
								Tyed into Annulus
	11:30							Pumped 25 sks down Annulus
								Pressure to 500 PSI
	11:45							Shut in
	11:45							Top off late w/ 35 sks cut
	15:00							Plug down at 3:00 pm
								Total in Production 185 sks cut