


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ness County. Sec. 25 Twp. 20S Rge. 21 (W)

Location as "NE/CNW/SE" or footage from lines. A/C SE/4 SE/4  
Lease Owner Barnett Oil Company  
Lease Name Martin "C" Well No. 1  
Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 7, 1967  
Application for plugging filed September 8, 1967  
Application for plugging approved September 7, 1967  
Plugging commenced September 7, 1967  
Plugging completed September 7, 1967  
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production - - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4413 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260 1/2'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pulled pipe to 600'; through drill pipe filled with 100 sacks cement plus 4% additional gell (125 sacks); pulled pipe to 240'; filled hole with 15 sacks to 270'; at 40' built solid plug and filled casing to surface with 10 sacks.

Completed at 3:00 A.M., 9-7-67.

(Well Log attached)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 14 1967

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor K & E Drilling, Inc.  
Address 719 Union Center Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. G. Gould, partner of Barnett Oil Co. of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. G. Gould  
411 First Nat'l Bank Bldg., Wichita, Ks.  
(Address)

Sworn to before me this 8th day of September, 1967

Mildred F. Willis  
Notary Public.



# DRILLER'S WELL LOG

OPERATOR: BARNETT OIL COMPANY  
411 First National Bank Bldg.  
Wichita, Kansas 67202

WELL NAME: #1 MARTIN  
LOCATION: C SE/4 SE/4  
Section 25-20S-21W  
Ness County, Kansas

CONTRACTOR: **K&E DRILLING, INC.**  
719 UNION CENTER BLDG.  
WICHITA, KANSAS

COMMENCED: August 27, 1967  
COMPLETED: September 7, 1967  
ELEVATION: 2225' Grd; 2231' D.F.  
2234' K.B.  
PRODUCTION: Dry

CASING RECORD:  
8-5/8" @ 261' w/180 sx.

ROTARY TOTAL DEPTH: 4413'

## FORMATION RECORD

*Depths shown indicate bottom of formations encountered.*

Surface Soil & Post Rock	62
Sand	78
Shale	195
Sand	215
Shale	850
Sand	1040
Shale	1380
Shale & Shells	1765
Lime	4413

RECEIVED  
STATE CORPORATION COMMISSION

SEP 13 1967

CONSERVATION DIVISION  
Wichita, Kansas

## CERTIFICATION

State of KANSAS }  
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

*H. L. Wilson*  
H. L. Wilson

Subscribed and sworn to before me this 12th day of September, 1967.

My Commission expires: 9-14-70

*Judie K. Eby*  
Judie K. Eby, Notary Public.

