

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 25 Twp. 20S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines 1980 FSL, 660 FEL

Lease Owner Cities Service Oil Company

Lease Name Martin "C" Well No. 2

Office Address Box 308, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 9 19 66

Application for plugging filed July 9 19 66

Application for plugging approved July 9 19 66


Plugging commenced July 10 19 66

Plugging completed July 10 19 66

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production -- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation m Depth to top Bottom Total Depth of Well 4426' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	510'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 4426' to 510' Heavy Mud
- 510' to 410' 30 sx cement
- 410' to 40' Mud
- 40' to base of cellar 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers Drilling, Inc. & Sun Oilwell Cementing Inc.
Address Box 359, Hoisington, Kansas Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

W. J. Devaney (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. J. Devaney*

(Address)

SUBSCRIBED AND SWORN to before me this 13 th day of XXXX July, 19 66

Bob L. Emerson

Notary Public.

My commission expires May 24, 1970

WELL RECORD

15.135.30248.0000

Company Cities Service Oil Company Well No. 2 Farm Martin "C"
 Location 1980' FSL and 660' FEL (Con. NE SE) Sec. 25 T. 20 R. 21W
KB 2225
 Elevation DF 2222, GL 2217 County Ness State Kansas
 Initial Prod. B&A Contractor Feel Brothers, Inc.
 Acid None Drlg. Comm. June 28, 1966
 T. D. 4426' Drlg. Comp. July 10, 1966

CASING RECORD:

8-5/8" (32#) at 510' cemented with 200 sx 50-50
 Pozmix, 2% CC and 78 sx
 Common, 2% CC.

FORMATION RECORD:

surface clay	0-40'
shale & red bed	1400
Anhydrite	1432
shale	1585
shale & shells	1985
shale & lime	3445
lime	4400
lime & chert	4405
lime & shale	4426 RTD

LOG TOPS:

Heebner	3748 (-1523)
Lansing	3799 (-1574)
Base Kansas City	4140 (-1915)
Ft. Scott	4315 (-2090)
Cherokee Shale	4334 (-2109)
Conglomerate	4362 (-2137)
Mississippi	4382 (-2157)

Log Total Depth 4430 = 4426 RTD.

SLOPE TESTS:

1650'	0°
2375'	1/4°
2589'	1/2°
2893'	1-1/2°
3225'	1-1/4°
3745'	1/2°
3880'	1/2°

RECEIVED
 STATE COMMISSION COMMISSIONER
 JUL 20 1966
 COMMISSIONER DIVISION
 MINERAL RESOURCES