

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS, 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-30208-00-00

LEASE NAME Martin C

WELL NUMBER 1

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 25 TWP. 20 RGE. 21 (X) or (W)

COUNTY Ness

Date Well Completed 6/23/66

Plugging Commenced 12/11/01

Plugging Completed 12/12/01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Zinszer Oil Company, Inc.

ADDRESS P.O. Box 211, Hays, Kansas 67601

PHONE(S) (785) 625-9448 OPERATORS LICENSE NO. 6239

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/11/01 (date)

by Mike Maier (XCC District Agent's Name).

Is ACO-1 filed? no if not, is well log attached? yes

Producing Formation Mississippi Depth to Top 4357 Bottom 4417 T.O. 4396 P.B.T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Oil	510	0	8 5/8	510	none
Perf 4388-93		4416	0	4 1/2	4416	1991'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Shot off csg at 1991, pulled csg to 1405', pumped 15sx gelfollowed by 50 sx 60/40 pozmix 6% gel, pulled csg to 650', pumped 80sx 60/40 pozmix 6% gel, pulled csg out of hole, top off 8 5/8 csg with 20sx 60/40 pozmix 6% gel, Note, on 12/11/01 rig crew spotted 6sx sand and dumped 2.5sx cement to seal off bottom of well.

Name of Plugging Contractor Swift Services License No. 32382

Address Ness City, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Zinszer Oil Company, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Perry S. Henman (Employee of Operator) ~~XXXXXXXXXXXXXX~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 211, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 28th day of February 2002, 02

[Signature]
Notary Public

My Commission Expires: August 24, 2002



OR

WELL RECORD

Company Cities Service Oil Company Well No. 1 Farm Martin "C"
 Location 1980' FSL and 1980' FEL (Gen. NW SE) Sec. 25 T. 20 R. 21W
 KB 2239
 Elevation DF 2236, EL 2231 County Ness State Kansas
 State Potential:
 Initial Prod. Pumped 117 bbls. oil, 3.6 bbls. wtr., 24 hrs. Contractor Peel Brothers, Inc.
 Acid None Drlg. Comm. May 30, 1966
 T. D. 4417, PBTD 4402 Drlg. Comp. June 10, 1966

CASING RECORD:

8-5/8" @ 510' cemented with 200 sx 50-50 Pozmix, 2% CC and 75 sx common, 2% CC.
 4-1/2" (9.5#) at 4416' cemented with 200 sx salt saturated common. Top cem. at 3390'.

FORMATION RECORD:

clay & lime	0-60
shale & shells	850
shale & sand	1116
shale & red beds	1416
Anhydrite	1450
shale & shells	2140
lime & shale	3628
lime	3743
lime & shale	4200
lime, shale & sand	4357
cherty lime	4383
chert	4417 RTD

HJL:ER
6-27-66

LOG TOPS:

Heebner	3743 (-1504)
Toronto	3761 (-1522)
Lansing	3791 (-1552)
Base Kansas City	4127 (-1888)
Ft. Scott	4299 (-2060)
Cherokee Shale	4320 (-2081)
Conglomerate	4347 (-2108)
Mississippi	4364 (-2125)
Log Total Depth	4417

COMPLETION:

Drilled out cement to PBTD 4402.
 Perforated Mississippi 4388-4393.

SLOPE TESTS:

2438'	1°
2690'	3/4°
3035'	1°
3440'	1°
3803'	3/4°
4007'	1/4°

RECEIVED
 MAR - 4 2002
 KCC WICHITA