


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

Ness County, Sec. 30 Twp. 17 Rgs. 21 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Okmar Oil Co.  
Lease Name Brenner Well No. #1  
Office Address 1130 Vickers KSB&T Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 10-26-73 19  
Plugging completed 10-30-73 19  
Reason for abandonment of well or producing formation  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Depth to top Bottom Total Depth of Well 4305' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4305'	3275.84'
				8 5/8"	273'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4275'. Mixed and ran 5 sacks cement thru dump bailer.

Squeezed hole with 3 sacks hulls - 20 sacks gel - 2 sacks hulls - 70 sacks cement 8 sacks gel. Released plug and 50 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 1 1973

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer  
Box 364 Great Bend, Kansas  
(Address)

Subscribed and Sworn to before me this 31 day of October, 1973.

Sidney D. Miller  
Notary Public.

My commission expires



DRILLERS' LOG

OKMAR OIL COMPANY  
1130 Vickers/KSB&T Bldg.  
Wichita, Kansas 67202

No. 1 Brennar  
C NE NE, Sec. 30-17S-21W  
Ness County, Kansas

Elevation: 2226 K.B.

Commenced: 5-19-73  
Completed: 6- 4-73

Surface Casing: 273.24' of  
8-5/8" used casing cemented  
w/200 sx 60-40 Posmix, 3%cc.  
5-19-73

FORMATION

DEPTH

Surface Hole	0 - 281
Shale	281 - 945
Sand & Shale	945 - 1200
Shale & Shells	1200 - 1400
Red Bed	1400 - 1520
Anhydrite	1520 - 1555
Shale & Salt	1555 - 2080
Shale & Lime	2080 - 2394
Lime	2394 - 2605
Lime & Shale	2605 - 3090
Lime	3090 - 3345
Lime & Shale	3345 - 3625
Lime	3625 - 4305 T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 24 1973  
CONSERVATION DIVISION  
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 6th day of June, 1973.

My Commission Expires:  
August 25, 1976

*Ella Priess*  
Ella Priess, Notary Public

