

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING REPORT
K.A.R.-82-3-117

API NUMBER 15-135-23,104.0000

LEASE NAME Brenner

WELL NUMBER #1

4620 Ft. from S Section Line

560 Ft. from E Section Line

SEC. 30 TWP. 17S RGE. 21 KEYor(W)

COUNTY Ness

Date Well Completed N/A

Plugging Commenced 2/24/98

Plugging Completed 2/24/98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Whitetail Crude, Inc

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE(S) (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/17/98 (date)

David P. Williams (KCC District Agent's Name).

ACO-1 filled? yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4289 Bottom 4293 T.D. 4400

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippian		0	284	8 5/8		0
		0	4400	5.5		0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from feet to feet each section.
Spot 35 sacks + 100# hullbs on bottom through tubing 4250'

Spot 160 sacks + 350# hulls @ 1500'

Top off with 40 sacks to surface

Pump 1/2 sack on backside to 500 PSI


Name of Plugging Contractor Halliburton Energy Services License No. _____

Address 1102 E 8th St, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well, as filed thereon, are true and correct, so help me God.



(Signature) Mike J. Fritzler

(Address) P O Box 544, Ness City, KS 67560-0544

SUBSCRIBED AND SWORN TO before me this 25th day of February, 19 98

Debra Kerr Notary Public

My Commission Expires: 4/20/2001

USE ONLY ONE SIDE OF EACH FORM

Form CP-
Revised 05-8
CONSERVATION DIVISION
Topeka, Kansas

Producer

15.135.23104.0000

GREAT GUNS



LOGGING

DIGITAL LOG

R. A. GUARD
LOG

COMPANY: WILLIAM BUCKLIN
WELL: BRENNER #1
FIELD: WILDCAT
COUNTY: NESS

FILE NO.: H-053801

STATE: KANSAS
COUNTRY: USA

LOCATION: 100' E DF C NE NE

SEC: 30 TWP: 17S RGE: 21W

DATE: 3/30/87

RUN NO.: 1

PERMANENT DATUM: CL
DRILLING MEASURED FROM: KB
LOG MEASURED FROM: KB
ABOVE PERMANENT DATUM: 5.0

DEPTH--DRILLER: 4350.0
DEPTH--LOGGER: 4851.0
BOTTOM LOG INTERVAL: 4294.8
TOP LOG INTERVAL: 3480.2

CASING DEPTH--DRILLER: 281.0
CASING DEPTH--LOGGER: .0
CASING DIAMETER: .000
BIT SIZE: 7.875

UNIT NO.: 64
LOCATION: HAYS, KS
RECORDED BY: D. LEGLEITER
WITNESSED BY: JOHN DAWSON

ELEVATIONS:

KB: 2228.0
DF: 0
CL: 2221.0

SERVICES:

CR
ENPC

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1998

CONSERVATION DIVISION
Wichita, Kansas

SOFTWARE VERSION:
3140