

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

DRILLING 15-185-01749-0002

API NUMBER COMPLETION 3-20,1934 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.) 6/86

LEASE OPERATOR ARGO OIL & GAS COMPANY OPERATORS LICENSE NO. 5398

ADDRESS P.O. BOX 3708 ENID, OKLAHOMA 73702 PHONE # (405) 233-6800

LEASE (FARM) GATES UNIT WELL NO. B-1 WELL LOCATION C-SW-NE/4 COUNTY STAFFORD

SEC. 27 TWP. 21S RGE. 13W or (W) TOTAL DEPTH 4165 PLUG BACK TD 4165

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. D-01,878

SURFACE CASING SIZE 12½" SET AT 210' CEMENTED WITH 95 SACKS

CASING SIZE 7" SET AT 3662 CEMENTED WITH 350 SACKS
5½" liner 3340'-3848' 225 SACKS

PERFORATED AT OPEN HOLE 3848-4165

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK PARTED JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run Tbg. to 690'. Casing collapsed at this point. Spot 50 sx Cmt plug. P.O.H. Pull 7" OD Csg. parted at 425'. Run Tbg. to 420'. Mix and pump Cmt. from 420' to Surface. Cap 12½" OD Csg. OVER

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO LOGS AVAILABLE IS ACC-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Based on approval date and contractor availability

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

ROBERT L. McGLINN PHONE # (316) 793-5467

ADDRESS P.O. BOX 849, 900 TENTH STREET, GREAT BEND, KANSAS 67530

PLUGGING CONTRACTOR BASED ON LICENSED CONTRACTOR AVAILABILITY _____ LICENSE NO. _____

ADDRESS _____ PHONE # () _____

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Robert L. McGlinn
(Operator or Agent)

DATE: 11-12-86

MAR 13 1986

CONSERVATION DIVISION
Wichita, Kansas

GATES UNIT B-1 SHORT HISTORY

This well was drilled and completed 3-20-34 as a producer.

4-16-48 Well converted to SWDW. Deepen from 3698 to 4165'. Ran 5½" liner 3340' to 3848' CMT. with 225 sx.

2-19-86 Set Baker RBP at 3295' with full Bore to test Csg. Csg. test at 500# from 3295' to 950' tested and held. Csg. leak 881'-912' Csg. bad from that point to surface. Dia-Log on location to find free point to back off 7" OD Csg. When torque up for back off Csg. parted at 421'. Released rig.

3-10-86 Rig up to retrieve B.P. at 3295'. Run Csg guide for alignment. P.O.H. ran Baker retrieving head and bumper sub and Tbg. to 980' stacked out. P.O.H. with Tbg. and tools.

3-11-86 Ran in hole with open end 2⁷/₈" OD Tbg. Tbg hung at 690'. P.O.H. Released rig leaving BP at 3295'.

3-11-86 I called Kansas State Corporation Commission District #1 Dodge City, Kansas. I talked with Mr. Steve Durrant on the problems with Gates Unit B-1. Mr. Durrant ok'd the procedure on the suggested method of plugging this well.



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1288

THIS NOTICE

JUN 13 1986

March 13, 1986

EXPIRES

WELL PLUGGING NOTICE

Gates Unit B-1 (SWD)
C SW NE/4
Sec. 27-21S-13W
Stafford County

ARCO Oil & Gas Company
P. O. Box 3708
Enid, OK 73702

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson

William R. Bryson, Director.

Please submit your proposal for plugging the above captioned well to

DIST. #1 302 West McArtor Dodge City, KS 67801 316-225-6760

five days prior to plugging the well (KAR-82-3-113).