

To: 1 120586
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
209 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-27
API NUMBER 15- 185-22,220.0000 2502
100' N of
SW NW NE, SEC. 31, T 21 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5050
Operator: Hummon Corporation
Name & Address: 400 One Main Place
Wichita, KS 67202

4390 feet from S section line
2310 feet from E section line
Lease Name Rex Well # 1
County Stafford 115.05
Well Total Depth 3540 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 260.73

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 27 Month: 6 Year: 19 91

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3539' w/100 sx cement, PBTB 3515', Perfs at 3257-3518' (5 sets)
1st plug sand back to 3200' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:15 p.m. Day: 27 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3200' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement,
Pumping pressure 0-600 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)
I (did / ~~did not~~) observe this plugging.

DATE 7-18-91
INV. NO. 32279

Signed Dean Rankin
(TECHNICIAN)