

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21169-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 31-21S-11W
1650 feet from N Section Line, 4950 feet from E Section Line
Lease/Unit Name: MELLIES Well Number: 3
County: STAFFORD Total Vertical Depth: 3553 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 3550 WITH 125 SX CMT
Surface Casing Size: 8.625 feet: 258 WITH 280 SX CMT

9115 47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2003 8:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING Phone: _____

Proposed Plugging Method: PUMP 50 SX CMT & 300# HULLS. PRESSURE TEST. PUMP DOWN ANNULUS WITH 150 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 07/16/2003 10:50 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3550'. PERFS AT 3522-25 & 3534-39'. ANHYDRITE @ 560'. PUMPED DOWN 4 1/2" CASING WITH 50 SX CMT - 300# HULLS - 200 SX CMT. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 250 PSIG. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS WITH 150 SX CMT. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 500 PSIG.

RECEIVED
JUL 24 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
JUL 18 2003
KCC Dodge City

Signed Richard W. Yacep
(TECHNICIAN)

INVOICED
DATE 7-24-03
INV. NO. 2004060110

[Handwritten signature]
Form CP-23