

To: 120734
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 3/61
NE SE SW, SEC. 31, T. 21 S, R. 11
990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5558
Operator: Dawson-Markwell Expl.
Name: _____
Address: 3620 N.W. 58th
Oklahoma City, OK 73112

Lease Name Mellies-Eason Well # 1
County Stafford
Well Total Depth 3538 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kincaid Well Service License Number 7252
Address P.O. Box 276, Ellinwood, KS 67526-0276

Company to plug at: Hour: 8:30 a.m. Day: 19 Month: 8 Year: 19 92
Plugging proposal received from Ed Markwell
(company name) Dawson-Markwell (phone) 405-947-2587

were: 4 1/2" at 3522', Open hole, Holes in casing from 730-1900'
1st plug run tubing in 4 1/2" casing to 3250' and spot 20 sx cement,
2nd plug pull tubing to 2400' and circulate 4 1/2" casing and 4 1/2" X 8 5/8" annulus with 40 bbl.
drilling mud, pull tubing to 730' and circulate cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:30 a.m. Day: 4 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug ran tubing to 3250' and spotted 20 sx cement plug in 4 1/2"
casing,
2nd plug pulled tubing to 2400' and circulated drilling mud with 40 bbls., pulled tubing to
750' and pumped in 230 sx cement. Cement did not circulate.
8/24/92 Ran line and found top of plug at 73'.
9/4/92 Filled with 1 yd. readymix.cement.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.
(If additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

INVOICED
DATE 10-6-92
INV. NO. 36312

Signed Duane Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1992
CONSERVATION DIVISION
WICHITA, KANSAS