

5 060145

10-26

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 159-22,130

W/2 SW , SEC. 15 , T 21 S, R 7 W/RX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3520

_____ feet from S section line

_____ feet from E section line

Operator: M.D.B. Operations, Inc.

Lease Name Engelland Well # 4-15

Name &

County Rice

113.10

Address 4500 S. Garnett, Suite #918

Well Total Depth 3480 feet

Tulsa, OK 74146

XXXXXXXXXX Pipe: Size 5-1/2" feet 3479/175 sx

Surface Casing: Size 8-5/8 feet 221

Abandoned Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Great Bend, KS

Company to plug at: Hour: _____ am Day: 26 Month: 10 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) _____

were: Sand to 3350' and cap w/5 sx cement - shoot off casing - pump 4 sx hulls
& mix with 25 sx cement, 10 sx gel, 8-5/8" plug, 125 sx cement, 60/40 poz 2% gel.

RECEIVED

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

11-10-88

NOV 10 1988

Plugging Proposal Received by Dist #2 Office CONSERVATION DIVISION
(TECHNICIANS)Plugging Operations attended by Agent?: All ☒ Part _____ None _____

Operations Completed: Hour: 10:15a Day: 26 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT Sanded to 3350' and capped w/5 sx cement - shot off casing -
pumped 4 sx hulls mixing in 25 sx cement, 10 sx gel, 8-5/8" plug, 125 sx cmet,
60/40 poz 2% gel.

Max Press 600# - Shut in Press 300#

Remarks: B.J. Titan #405417 Perfs 3410-3430' Rec. 2332' 5-1/2"

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE

11-17-88

Signed

R. Phil Worley
(TECHNICIAN)

INV. NO.

23004