

1 120865

12-8

API NUMBER 15- 185-01,043.0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW, NE SE, SEC. 26, T 21 S, R 12 W/E  
2310 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3672  
Operator: Helm Energy Company  
Name & Address: 6104 E. 32nd St., Ste. 207  
Tulsa, OK 74135

Lease Name Widener Well # 1  
County Stafford 121.94  
Well Total Depth 3752 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 233

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 8 Month: 12 Year: 19 93

Plugging proposal received from John Helm

(company name) Helm Energy Company (phone) 918-665-3740

well: 5 1/2" at 3747' w/75 sx cement, PBD 3750', Perfs at 3554-94'

1st plug sand 5 1/2" casing back to 3500' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 8 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3500' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1750' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this report)

observe this plugging.

INVOICED

DATE DEC 14 1993

INV. NO. 39509

RECEIVED STATE CORPORATION COMMISSION  
DEC 10 1993  
Signed Duane Rankin  
TECHNICAL CONSERVATION DIVISION  
Wichita, Kansas  
FORM CP-2  
Rev. 01-