

2-3

To: 051779
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,946.0000
150' S of
NW SW SE, SEC. 26, T 21 S, R 12

TECHNICIAN'S PLUGGING REPORT
Operator License # 6039
Operator: L.D. Drilling, Inc.
Name: RR 1, Box 183 B
Address: Great Bend, KS 67530

840 feet from S section line
2310 feet from E section line
Lease Name Bernice Well # 1
County Stafford
Well Total Depth 3674 149.41
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling Inc. License Number 6039
Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 9 p.m. Day: 3 Month: 2 Year: 19 94

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling Inc. (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 498-518'
1st plug at Arbuckle with 50 sx cement, 2nd plug at 600' with 50 sx cement,
3rd plug at 290' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

2-9-94
RECEIVED
STATE CORPORATION COMMISSION
FEB - 9 1994
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11 p.m. Day: 3 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 3580' with 50 sx cement,
2nd plug at 600' with 50 sx cement,
3rd plug at 290' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
Additional description is necessary, use BACK of this form.
I (XXXX) will observe this plugging.

INVOICED
FEB 11 1994
DATE
INV. NO. 39917

Signed Richard W. Lacey (TECHNICIAN)

EFFECTIVE DATE: 11-20-93

State of Kansas 15-185-22,946.0000

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

DISTRICT: 1
SEA7: Yes No

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: December 27 1993
month day year

Spot 150' South
NW SW SE Sec 26 Twp 21 S Rg 12 XX East West

OPERATOR: License # 6039
Name: L. D. DRILLING, INC.
Address: R.R. 1 BOX 183 B
City/State/Zip: GREAT BEND, KS. 67530
Contact Person: L. D. Davis
Phone: (316). 793-3051

840 feet from South / North line of Section
2310 feet from East / West line of Section
IS SECTION XX REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: STAFFORD
Lease Name: BERNICE Well #: 1
Field Name: Max North

CONTRACTOR: License #: 6039
Name: L. D. DRILLING, INC.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ..X Infield ..X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... O/W/O ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Arbuckle

Nearst lease or unit boundary: 330
Ground Surface Elevation: 1821 feet MSL

If O/W/O: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Water well within one-quarter mile: X yes no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 220'
Surface Pipe by Alternate: XX 1 2

Length of Surface Pipe Planned to be set: 250'
Length of Conductor pipe required: none

Projected Total Depth: 3700'
Formation at Total Depth: Arbuckle

Water Source for Drilling Operations:
X well ... farm pond ... other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Old Permit #:
Will Cores Be Taken? yes no
If yes, proposed zone:

Exp. 5/15/94

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met.

250' Alt. I Req.
RECEIVED
STATE CORPORATION COMMISSION
FEB - 9 1994

CONSERVATION DIVISION
Wichita, Kansas

4410

Pusher Bessie
SPUD DATE 1-24-94 - Spud 1/21/94
INIT. Sm
LENGTH SURFACE PLANNED 250
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 5 3/4 @ 260 CONDUCTOR
ANHYDRITE T- 498 B- 518 ELEVATION
TD 2674 FORMATION Arbuckle

RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ 50 Ft. W/ 50 SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 600 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 240 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well) Pond
Hauling
TECHNICIAN R-L DATE
TYPE OF CEMENT 60/40 poz 6% grt
STARTING TIME 9:00 (AM/PM) DATE 2-3-94
COMPLETION TIME 11:00 (AM/PM) DATE 2-3-94
CEMENT COMPANY Allied