

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21942-00-00
Spot: NWSWSENW Sec/Twnshp/Rge: 8-14S-31W
2296 feet from N Section Line, 1491 feet from W Section Line
Lease Name: JESERICH Well #: 1-8
County: GOVE Total Vertical Depth: 4660 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4640		165 SX
SURF	8.625	224		150 SX
T1	2.375	4613		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2017 1:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: LARRY KARLIN Company: LARIO OIL & GAS COMPANY DBA Phone: (620) 277-2149

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 2369' w/670 sx cement.
Perforations: 4493' - 4512'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2017 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4460' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 3600' and pumped 75 sx cement. Pulled tubing to 2609' and pumped 75 sx cement. Pulled tubing to 1585' and pumped 120 sx cement. Good circulation of cement. Pulled tubing out and topped casing off with 15 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 38.85273 -100.79362

Perfs:

Top	Bot	Thru	Comments
4496	4512		
4493	4512		

KCC WICHITA
DEC 04 2017
RECEIVED

INVOICED
JAN 03 2018

Remarks: HURRICANE CEMENT TICKET # 54968

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

NOV 16 2017