

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21850-00-00
Spot: NESESWNE Sec/Twnshp/Rge: 33-14S-31W
2170 feet from N Section Line, 1500 feet from E Section Line
Lease Name: THEIS RANCH Well #: 1-33
County: GOVE Total Vertical Depth: 4400 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4394		175 SX
SURF	8.625	215		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2017 9:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: MIKE KEETERLING Company: LARIO OIL & GAS COMPANY DBA Phone: (620) 277-2149

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 2185' w/395 sx cement.
Perforations: 3776' - 3782' and 3866' - 3872'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2017 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3760' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2948' and pumped 75 sx cement. Pulled tubing to 1924' and pumped 75 sx cement. Pulled tubing to 900' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped casing off with 15 sx cement. Tied on to backside and squeezed with 20 sx cement. Shut in pressure 300 psi.

GPS: 38.79548 -100.76843

Perfs:

Top	Bot	Thru	Comments
3866	3872		
3776	3782		

KCC WICHITA
DEC 04 2017
RECEIVED


INVOICE-D
JAN 03 2018

Remarks: QES TICKET # 54965

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

NOV 16 2017