

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20702-00-01
Spot: S2N2SWSE Sec/Twnshp/Rge: 16-6S-36W
680 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ROBISON "C" OWWO Well #: 1
County: THOMAS Total Vertical Depth: 4215 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4216		230 SX
SURF	8.625	411		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2017 11:00 AM
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: L. D. DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4 % gel cement w/ 800 # hulls.
8 5/8" surface casing set at 411' w/ 250 sx cement.
4 1/2" production casing set at 4216' w/ 230 sx cement.
TD 4215' PBTD 4167'
Perforations: 3988'-3990', 3971'-3973', 3954'-3957'.
No two stage cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2017 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 3033' & 2180'. Ran tubing to 3910' and pumped 90 sx cement with 200 # hulls. Pulled tubing to 2640' and pumped 90 sx cement with 100 # hulls. Pulled tubing to 1343' and pumped 100 sx cement with 50 # hulls. Cement circulated to surface. Pulled tubing to surface. Connect to 4 1/2" production casing and pumped 25 sx cement. Connect to 8 5/8" surface casing and pumped 80 sx cement. Maximum pressure 100 psi.

GPS: 39.52789N -101.34082W

Perfs:

Top	Bot	Thru	Comments
3988	3990		
3971	3973		
3954	3957		

INVOICED
JAN 03 2018

Remarks: GREEN OILFIELD SERVICES RIG AND SOS OILFIELD SERVICES LLC CEMENT TICKET # 614.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

DEC 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3