

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20641-00-01
Spot: NENWSESE Sec/Twnshp/Rge: 17-21S-10W
1255 feet from S Section Line, 710 feet from E Section Line
Lease Name: FLORA Well #: 2
County: RICE Total Vertical Depth: 1670 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION INC.
Address: PO BOX 354
CHASE, KS 67524

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | 4.5 | 1400 | | |
| PROD | 4.5 | 1670 | | 150 SX |
| SURF | 8.625 | 216 | | 150 SX |
| T1 | 2 | 1506 | | |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/29/2017 9:30 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 546-3388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 11/29/2017 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS AND TUBING. SET CIBP AT 1400' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1250', 850', AND 265'. RUN TUBING TO 1250' AND PUMP 35 SX'S CEMENT WITH 2% CC. LET SET FOR 1 HOUR. TAG CEMENT AT 1050'. PUMPED 35 SX'S WITH 2% CC AT 850'. PULL TUBING TO 265' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1444 | 1448 | | CSG |
| 1424 | 1428 | | CSG |

INVOICED
JAN 03 2018

Remarks: GEMINI TICKET #3607. BASIC SERVICES #16141. TA - N.O.V. WELL.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

18