

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20646-00-01
Spot: W2W2SE Sec/Twnshp/Rge: 17-21S-10W
1365 feet from S Section Line, 1900 feet from E Section Line
Lease Name: FLORA Well #: 3
County: RICE Total Vertical Depth: 3420 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION INC.
Address: PO BOX 354
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	1400		
CIBP	4.5	1500		
PROD	4.5	3419		475 SX
SURF	8.625	215		175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/28/2017 10:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: RANDY GINEST Company: RAMA OPERATING CO. Phone: (620) 546-3388

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 11/28/2017 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS & TUBING. SET CIBP AT 1400' AND CAP WITH 2 SX'S CEMENT. PERFORATE AT 1250', 850', AND 265'. RUN TUBING TO 1250' AND PUMP 35 SX'S WITH 2% CC. PULL TUBING UP TO 850' AND WAIT 1 HOUR. TAG CEMENT AT 1050'. PUMPED 35 SX'S CEMENT WITH 2% CC AT 850', PULLED TUBING TO 265' AND CIRCUALTED CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
1424	1428		CSG

INVOICED
JAN 03 2018

Remarks: GEMINI PERF TICKET #3512. BASIC SERVICES #16140. TA - N.O.V. LETTER SENT.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)