

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21443-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 32-22S-34W
1268 feet from S Section Line, 1245 feet from E Section Line
Lease Name: DICK Well #: 2
County: FINNEY Total Vertical Depth: 2800 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2799	0	WITH 485 SX CMT
SURF	8.625	295		WITH 270 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/06/2017 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: DAVID Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/07/2017 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAK. TBG IS STUCK. 12/6/17: DROP STANDING VALVE. LOAD & TEST TBG TO 500#. CUT TBG AT 2000'. PULL TO 1970' & SPOT 65 SX CMT WITH 150# HULLS UP TO 1000'. RUN CBL. TOC @ 140'. SDON. 12/7/17: TIH WITH TBG & TAG TOC @ 1134'. CIRCULATE CMT FROM 1100' TO 0' WITH 65 SX CMT. TOP OFF WITH 10 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS & PRESSURE TO 400#.

Perfs:

Top	Bot	Thru	Comments
2550	2554		
2494	2516		

INVOICED
JAN 08 2018

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed _____

Ken Jehlik
SA

(TECHNICIAN)

RECEIVED
DEC - 8 2017
KCC DODGE CITY