

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-20103-00-00
Spot: NW Sec/Twnshp/Rge: 19-31S-38W
2939 feet from S Section Line, 3884 feet from E Section Line
Lease Name: REYNOLDS Well #: 2-19
County: STEVENS Total Vertical Depth: 2900 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		632		
PROD	5.5	2899	0	WITH 400 SX CMT
SURF	8.625	555		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/12/2017 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JASON PHELPS Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: TBG STUCK IN HOLE. CUT TBG ABOVE FILL @ 1300' OR DEEPER. PLUG AT TOP OF FISH WITH 60 SX CMT WITH 200# HULLS & 3% CC. WOC & TEST CASING TO 500 PSI., RUN CBL TO DETERMINE IF THERE IS CMT. PEFORATE AT 580' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2017 4:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CUT TBG AT 1680'. 1ST PLUG AT 1680' WITH 60 SX CMT WITH 200# HULLS & 3% CC. WOC & TRY TO TEST. WOULDN'T TEST. TAGGED CMT AT 1610'. SET CIBP @ 632' & TESTED CASING TO 500 PSI. HOLDING. RUN CBL & FOUND NO CMT. 2ND PLUG PERFORATE AT 585' WITH 210 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
2701	2855		
RECORDED JAN 03 2018			

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed

Kenny Sullivan
SA

(TECHNICIAN)

RECEIVED
DEC 14 2017
KCC DODGE CITY