

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
256 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00799-00-00  
Spot: NENENESW Sec/Twnshp/Rge: 6-23S-33W  
2550 feet from S Section Line, 2769 feet from E Section Line  
Lease Name: CORN Well #: 1  
County: FINNEY Total Vertical Depth: 2667 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, LLC  
Address: 600 TRAVIS STE 1400  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2550		
PROD	5.5	2645	0	WITH 700 SX CMT
SURF	8.625	388		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2017 10:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: DAVID Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2550'. RUN TBG TO 2500' & SPOT 80 SX CMT. PULL TO 1500' & ATTEMPT TO BREAK CIRCULATION WITH WATER. SPOT 150 SX CMT WITH 300# HULLS TO SHUT OFF CASING LEAK. TOOH WITH TBG & TOP OFF 5 1/2" CASING WITH CMT. TOP OFF ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/05/2017 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2550' PREVIOUSLY SET. RUN TBG & TAG CIBP @ 2550'. SPOT 80 SX CMT FROM 2550' TO 1780'. PULL TO 1512' & CIRCULATE CMT TO SURFACE WITH 155 SX CMT & 240# HULLS. TOOH WITH TBG & TOP OFF WITH 10 SX CMT. ATTEMPT TO PUMP DOWN ANNULUS @ 800 PSI. COULD NOT. FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2645	2667		
2590	2630		


WORKED  
JAN 03 2018

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
DEC - 7 2017  
KCC DODGE CITY

JA