

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-24115-00-00  
Spot: NWSEWNNE Sec/Twnshp/Rge: 10-17S-11W  
4296 feet from S Section Line, 1693 feet from E Section Line  
Lease Name: KRAFT Well #: 3A  
County: BARTON Total Vertical Depth: 3698 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3358		150 SX
SURF	8.625	360		175 SX

Well Type: SWD UIC Docket No: D24629.0 Date/Time to Plug: 11/21/2017 9:00 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.  
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed  
Plugging  
Method:

Ordered 200 sx of Class A Cement w/3% cc., 250 sx of 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/21/2017 1:30 PM KCC Agent: RAY DINKEL

**Actual Plugging Report:**

Perforated at 1400', 675' and 300'. Ran tubing to 3300' and pumped 75 sx hot cement w/100 # hulls. Pulled tubing to 2800' and pumped 12 sx gel followed by 55 sx hot cement w/100 # hulls. Pulled tubing to 1700' and pumped 70 sx hot cement w/100 # hulls. Pulled tubing to 700' and pumped 75 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 20 sx cement. Circulated cement out of braden head and around well. Shut in casing with 200 psi.

GPS: 38.59170 -098.52267

**Perfs:**

Top	Bot	Thru	Comments
3358	3698		

KCC WICHITA  
DEC 04 2017  
RECEIVED

Remarks: SWIFT SERVICES TICKET # 230872

Plugged through: TBG

INVOICED  
JAN 02 2018

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

NOV 22 2017