

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-20612-00-02
Spot: NESENE Sec/Twnshp/Rge: 36-6S-26W
3629 feet from S Section Line, 382 feet from E Section Line
Lease Name: HORTON Well #: 2
County: SHERIDAN Total Vertical Depth: 3944 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

PROD 4.5 3944 200 SX

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

SURF 8.625 319 180 SX

Well Type: EOR

UIC Docket No: E15006.2

Date/Time to Plug: 12/04/2017 8:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO LLC

Phone: (316) 265-3311

Proposed DV Tool at 2160' w/400 sx cement.
Plugging Casing leaks at 2260' - 2289' and 2734' - 2762'.
Method: Loc set stuck at 3753'.

Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: DARREL DIPMAN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/04/2017 2:10 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 3723'. Global pumped 75 sx cement w/150 # hulls. Pulled tubing to 2812' and pumped 90 sx cement w/300 # hulls. Pulled tubing to 1400' and pumped 100 sx cement. Lost circulation. Pulled tubing to 723' and pumped 45 sx cement w/50 # hulls. Cement circulated. PTOH. Tied onto backside and pumped 15 sx cement. Shut in pressure 300 psi. Stuck hose in 4 1/2" casing to top off and pumped 75 sx cement. Ran out of cement. Shut down for 2 hours waiting on more cement. Pumped 30 sx common cement from Hill City redi-mix. Casing full.

Top	Bot	Thru	Comments
3830	3833		
3778	3781		
3750	3756		
3700	3703		

GPS: 39.48997 -100.16338

Remarks:

Plugged through: TBG

RECEIVED
JAN 02 2018

District: 04

Signed



(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

DEC 20 2017

CONSERVATION DIVISION
WICHITA, KS

DEC 12 2017

Form CP-2/3