

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-10006-00-01
Spot: SESE Sec/Twnshp/Rge: 27-21S-34W
651 feet from S Section Line, 639 feet from E Section Line
Lease Name: GOBLEMAN A Well #: 2
County: FINNEY Total Vertical Depth: 4703 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4625		
PROD	5.5	4634	0	WITH 550 SX CMT
SURF	10.75	284		WITH 225 SX CMT

Well Type: EOR UIC Docket No: E09779.7 Date/Time to Plug: 12/04/2017 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KIRK TAYLOR Company: ELDRIDGE Phone: (316) 636-2090

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2017 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF 2 7/8" TBG FISH AT 890'. TBG IS SEVERELY CORRODED AND ATTEMPTS TO FISH TBG OUT ANY DEEPER WERE UNSUCCESSFUL. 11/14/12: BOND LOG RAN 11/14/12 SHOWS CMT FROM 4239' TO 2450', 1880' TO 1510', 1300' TO 465'. PERFORATED AT 396' & CIRCULATED CMT TO SURFACE. 12/4/17: RAN PACKER ON 2 7/8" TBG TO 860'. WOULD NOT SET. RESET AT 830'. HOLDING. PRESSURE ANNULUS TO 500#. INJECTION RATE DOWN TBG 1 1/2 TO 2 BPM AT 1000' TO 1500 PSI. MIX & PUMP 55 SX CMT AND WELL SQUEEZED OFF AT 1500 PSI WITH 30 SX CMT PUMPED BELOW PACKER. RELEASE PACKER & SPOT 25 SX CMT FROM 830' TO 630'. FILL CASING WITH CMT FROM 630' TO SURFACE THROUGH OPEN ENDED TBG WITH 100 SX CMT. TOP OFF WITH 10 SX CMT. ATTEMPT TO PUMP CMT DOWN ANNULUS AT 300 PSI. WAS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4272	4284		

INVOICED
JAN 03 2018

Remarks: USED CLASS A COMMON CEMENT BY QES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SR

(TECHNICIAN)

RECEIVED
DEC - 8 2017

SR