

1 051740

11-5

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,749.0000  
50' W of C  
N/2 SE SE, SEC. 9, T 20 S, R 24 W/8

990 feet from S section line  
710 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Lease Name Bankoff Minerals Well # 4

Operator: Bankoff Oil Company

County Ness 143.91

Name & Address P.O. Box 1374

Well Total Depth 4428 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 315.92

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 5 Month: 11 Year: 19 93

Plugging proposal received from Richard

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

vers: 5 1/2" at 4404' w/100 sx cement, Open hole 4404-28'

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,

Spot plugs through casing:

2nd plug at 1550' with 10 sx gel and 50 sx cement,

3rd plug at 900' with 80 sx cement,

4th plug at 350' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:15 p.m. Day: 5 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,

Spotted plugs through casing:

2nd plug at 1550' with 10 sx gel and 50 sx cement,

3rd plug at 900' with 80 sx cement,

4th plug at 350' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1928' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

**INVOICED**

RECEIVED  
STATE CORPORATION COMMISSION

DATE NOV 16 1993

Signed Richard W. Lacey  
(TECHNICIAN)

WV. NO. 39188