

1 070206

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,202.0000

C S/2 S/2 NW SEC. 8, T 20 S, R 24 W/E

2970 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Betz Well # 5-C

Operator: Palomino Petroleum

County Ness 143.59

Name & Route 5, Box 51-C

Well Total Depth 4418 feet

Address Newton, Kansas, 67114

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 326'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 12 Month: 8 Year: 1986

Plugging proposal received from Vernon Dutz

(company name) Kelso (phone) 316-938-2457

Elevation 2332KB

were: 5 1/2" at 4393' PBD 4350' Perfs at 4283'-4301' Anhydrite 1569'

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 12 sx gel, 1 sack hulls, release 8 5/8 rubber plug and pump 175 sx cement.

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 12 Month: 8 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sand back to 4200' and dump 4 sx cement on top of sand

through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 12 sx

gel, 1 sack hulls, released 8 5/8 rubber plug and pump 175 sx cement.

Maximum pressure 800 psi and shut in 500.

Remarks: Recovered 2800' 5 1/2 casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 8-20-86

Signed Dan Goodrow

(TECHNICIAN)

INV. NO. 14778