

To: 1 070620

API NUMBER 15-135-21,885.0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
12-5-88

NE NE SW, SEC. 8, T 20 S, R 24 W/EX
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8572

Lease Name Miller Well # 1

Operator: Reach Oil Corporation

CONSERVATION DIVISION
Wichita, Kansas

County Ness 142.25

Name & Address
229 East William, Suite 500
Wichita, KS 67202

Well Total Depth 4377 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 243

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10:30 a.m. Day: 30 Month: 11 Year: 19 88

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling Service (phone) 316-675-8349

were: 4 1/2" at 4442' PBSD 4402' Perfs at 4360-4366'

Perfs were squeezed off and never was drilled out. Going to pressure up. If it doesn't hold, 1st plug pump 1 sx hulls and 20 sx cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 130 sx cement.

Plugging Proposal Received by Paul Luthi & Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 30 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement,

2nd plug pumped 50 sx cement, at 1400',

3rd plug pumped 80 sx cement at 780',

4th plug pumped 40 sx cement at 280',

5th plug pumped 10 sx cement at 40'. Pumped through casing. Did circulate.

Remarks: Used Class A cement by Midwest Casing Pulling. Recovered 2100' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(If ~~not~~ observed) observe this plugging.

DATE DEC 8 1988

Signed Dan Goodson (TECHNICIAN)

INV. NO. 23270 11-30

JAN 06 1989