

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-20065-00-00  
Spot: CSESE Sec/Twnshp/Rge: 6-20S-24W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: WESTERMEYES A Well Number: 1  
County: NESS Total Vertical Depth: 4392 feet

Operator License No.: 32000  
Op Name: ALB, INC.  
Address: PO BOX 173  
GREAT BEND, KS 67530

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 245 WITH 150 SX CMT  
Production: Size 5.5 feet: 4380 WITH 160 SX CMT  
Liner: Size feet: 8 1/2 .74

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/27/2001 1:50 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MIKE Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 4330' & 5 SX CMT. 1ST PLUG AT 1600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 790' WITH 80 SX CMT. 3RD PLUG AT 280' WITH 50 SX CMT. 4TH PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG  
Date/Time Plugging Completed: 06/27/2001 3:50 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

OPEN HOLE FROM 4380-92'. SANDED TO 4300' & 4 SX CMT. PULLED STRETCH AND COULDN'T PULL ENOUGH TO PLUG AT 1600'. SHOT AT 800' & PUMPED 10 SX GEL & 80 SX CMT. SHOT AT 300'. WOULDNT COME LOOSE. SHOT AT 240'. PUMPED 40 SX CMT. PULLED CASING & TOPPED OFF WITH 20 SX CMT. HOLE STAYED FULL.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 6 2001

CONSERVATION DIVISION

INVOICED

DATE 7-6-01

NO. 2002060018

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 240' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)  
JUL 02 2001