

1 070185

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,687-0000

C SW NE, SEC. 6, T 20 S, R 24 W7E

3300 feet from S section line

1980 feet from E section line

Lease Name Betz Well # 2

County Ness 143.52

Well Total Depth 4416 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 605

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Operator: Vincent Oil Corp.
Name & Address 125 North Market, Suite 1110
Wichita, KS 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 am Day: 21 Month: May Year: 19 86

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4405' Open hole from 4405-15'

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer

2nd plug attempted recovery at 2800', 2400', 2000', 1700', 1500', 1250', 1000', 900'

and 800'. Told Mark to plug top by pumping 400 sx 60/40 Pozmix 6% gel and recirculate.

Plugging Proposal Received by Don C. Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 21 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of

sand through bailer, 2nd plug - pipe shot at 2800', 2400', 2000', 1700', 1500',

1250', 1000', 900', and 800'. 8 5/8" would not take. Pressured to 500 psi.

400 sx cement down 4 1/2".

Maximum pressure 1000 psi and shut in 300 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE JUN 3 1986

INV. NO. 14046

Signed Don Goodrow (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUN 02 1986 CONSERVATION DIVISION WICHITA, KANSAS